

SECTION 10 ADJUSTMENT OF CASTINGS

10.01 DESCRIPTION

This work shall consist of adjusting castings for City-owned facilities to conform with the new elevation of the street and in conformance with the Standard Specifications and Details.

10.02 ADJUSTMENT

All castings for City-owned facilities shall be brought to finish grade after the final pavement lift has been installed. The manhole openings shall be temporarily covered by suitable means. For street reconstructions or asphalt repairs on existing streets, manholes and valves shall be raised and concrete placed within three working days after permanent pavement wearing course has been placed. The necessary portions of the subgrade, base and pavement shall be neatly cut away, the manhole built up, and the frames set to a grade flush with the surface of the adjacent pavement. The surrounding area from which the pavement, base or subgrade has been removed shall be backfilled to within 2 inches of the surface. The remaining 2 inches shall be paved with ½ inch maximum asphalt concrete and compacted with a 3-ton pneumatic steel drum roller. The work shall be performed so as to present a neat and thorough workmanlike appearance upon completion.

10.03 MEASUREMENT AND PAYMENT

Unless specifically shown as an item of work on the proposal form, the adjustment of castings shall be considered included in other items of work and no additional compensation will be made for labor, materials or equipment needed.